

Index
File No. N-15

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____

T. 4 S R. 32 E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM

T 4 S R 32 E

$\frac{1}{4}$ $\frac{S 15}{S 22}$



1977

DESCRIBE CORNER MONUMENT FOUND

Found 2½" iron pipe with ¾" brass cap (as shown in corner diagram) in mound of stone.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A 17" ponderosa pine brs N50¼° E, 37.5' with scribing visible. Badly rotted ponderosa pine stump size indeterminate, no scribing visible brs N6¼° W, 29.8'.
A 12" ponderosa pine snag brs S17½° E, 65.2' with scribing visible.

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls on South slope at Westerly edge of road.

Signature

Will R. Webb

Title

Land Surveyor

Division

Headquarters

Pendleton, Ore.

Date

6-03-92

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set steel fence post next to corner with sign 54-9. attached.
Compass declination 18° East.

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New bearing trees established:

A 14" ponderosa pine brs S81/2°E, 43.9' scribed 1/4S22 BT.

A 13" ponderosa pine brs S63°W, 15.5' scribed 1/4S22 BT

A 12" ponderosa pine brs N40 1/4°W, 32.1' scribed 1/4S15 BT.

New BT's have a brass washer stamped PLS 1106 nailed to face of blaze.

Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

10

Work Done By W.R. Wells Title Land Surveyor Date 6-03-92 State Registration No. ORLS 1106
or Agency

Certified Cor. Record Prepared ? Yes Filed At Umatilla County Surveyor Date 7-92

11

REMARKS

12

Index File No. N-15 T. 4 S R. 32 E M. Tract or Surv. No. Cor. 13