

USDA FOREST SERVICE  
Index

CORNER RECORD (SEARCH)

File No. T.25-22.25  
T.4S., R.32E.  
Meridian: Willamette

R.D.: N.F.J.D.  
N.F.: UMATILLA

Co. Survey No:  
County: Umatilla

CORNER DIAGRAM

DESCRIBE CORNER MONUMENT FOUND

S25  
NW-NE-SW  
1/256  
1994  
PLS 2405

None. Corner established this survey.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None. Corner established this survey.

PHOTO ID DATA

Photo No.  
Filed At  
Object ID

PLANE CO-ORD

State Zone

X

Y

Estab. By

DESCRIBE CORNER LOCATION:

Corner falls on gentle S-E slope of P.Pine and D.Fir

Signature:



Title: Land Surveyor

Date: 10/26/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.  
Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown  
on the DIAGRAM, 8" in the ground and raised a mound of earth and stone, 4  
ft. dia. x 2 ft. high. From Which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE  
Pond. Pine, 8" dia., bears N68°46'W, 37.0 ft., scribed: NW-NE-SW 1/256 S25 BT  
Pond. Pine, 12" dia., bears N62°02'E, 20.0 ft., scribed: NW-NE-SW 1/256 S25 BT  
Measurements to BT's taken with an Electronic Tacheometer with bearings  
based on the survey control network. Set steel fence post with Land Survey  
Monument (54-9) and Property Boundary (54-2) signs 5' north and west of the  
monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe  
as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and  
Land Survey Monument (54-9) signs on back of each tree as required.  
Painted a 6" red band above Bearing Trees signs.

Work Done by: Susan E. Newstetter Dr. Land Surveyor No. 2405 Date: 10/26/94  
Certified Cor. Record Prepared?  Yes  No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. T.25-22.25 T.4S., R.32E., W.M.