


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

P-14

History of original corner establishment:

None. Corner established as part of this survey.



Description of corner evidence found:

None.

Description of monument and accessories I established to perpetuate the original location of this corner:

At position established by survey...

Set a 2 1/2" X 30" aluminum pipe with 2 1/2" aluminum cap 22" in ground surrounded with mound of earth and stone set steel fence post next to corner and attached signs 54-2 & 54-9. Cap marked as shown in corner diagram.

New bearing trees established:

- A 18" western larch brs N42°W, 9.2' scribed CW1/16S22 BT.
- A 13" western larch brs N59°E, 37.6' scribed CW1/16S22 BT.

New BT's have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

Compass declination 18° East.

I hereby certify that the above corner monument was properly established to U.S.F.S. standards by me on June 12, 1992.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of... County Surveyor ..... County of... Umatilla  
Oregon ..... I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
Umatilla County Surveyor  
Date 7-92  
Rec'd By AK  
No. 92-80-B

P-14  
★ GPO—788-276