


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

P-15

History of original corner establishment:

None. Corner established as part of this survey.



Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

At position established by survey...

Set a 2 1/2" X 30" aluminum pipe with 2 1/2" aluminum cap 21" in ground surrounded with mound of earth and stone set steel fence post next to corner and attached signs 54-2 & 54-9. Cap marked as shown in corner diagram.

New bearing trees established:

- A 17" ponderosa pine brs N78 1/2° W, 62.6' dist mkd C1/4S22 BT.
- A 11" ponderosa pine brs N21° W, 17.8' dist mkd C1/4S22 BT.
- A 15" ponderosa pine brs N5° E, 39.6' dist mkd C1/4S22 BT.
- A 12" ponderosa pine brs N51° E, 40.0' mkd C1/4S22 BT.

New BT's have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

Compass declination 18° East.

I hereby certify that the above corner monument was properly established to U.S.F.S. standards by me on June 12, 1992.

REGISTERED PROFESSIONAL LAND SURVEYOR
---

*William R. Wells*

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106
---

Office of... County Surveyor ..... County of... Umatilla .....  
 State of... Oregon ..... , I hereby certify that the within instrument was filed in this office  
 for record on the..... day of..... , 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
 Umatilla County Surveyor  
 Date 7-9-92  
 Rec'd By [Signature]  
 No. 92-80-B

*P-15*

★ OPO-788-276