

INDEX No. P-20

History of original corner establishment:

None. Corner established this survey.

DIAGRAM
T4S R32E
E1/16
C-----C
S23
1994
PLS 2405

Description of Corner Evidence Found:

None. Corner established this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 26" in the ground.

From Which:

Douglas Fir, 18" dia., bears N32°42'W, 53.5 ft., scribed: C-E1/16 S23 BT

Douglas Fir, 12" dia., bears S26°28'W, 23.8 ft., scribed: C-E1/16 S23 BT

Measurements to BT's taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' north and south of the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs.

REGISTERED PROFESSIONAL LAND SURVEYOR
Susan E. Newstetter
OREGON JULY 27, 1989
SUSAN E. NEWSTETTER 2405
Renewal Date: 12/31/96

This work was performed by:
Susan E. Newstetter PLS 2405
Witnessed by: Rick Saul and
Rick Pewonka
November 2, 1994

RECEIVED BY
Umatilla County Surveyor
Date 1-95
Rec'd By SK
No. 95-15-B

Office of _____ County of _____ State of _____ I hereby certify that the within instrument was filed in this office for record on the _____ day of _____, 19____ by _____ (COUNTY OFFICIAL) _____ (DEPUTY) P-20