

USDA FOREST SERVICE

CORNER RECORD (SEARCH)

Index

File No. P-24

R.D.: N.F.J.D.

Co. Survey No:

T.4S., R.32E.

N.F.: UMATILLA

County: Umatilla

Meridian: Willamette

CORNER DIAGRAM | DESCRIBE CORNER MONUMENT FOUND

T4S R32E |

E1/16 |

None. Corner established this survey.

C-----C |

S24 |

1994 |

PLS 2405 |

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None. Corner established this survey.

PHOTO ID DATA |

Photo No. |

Filed At |

Object ID |

PLANE CO-ORD |

State Zone |

X |

Y | DESCRIBE CORNER LOCATION:

Estab. By |

Corner falls on west slope of D. Fir and W. Fir. E-W draw
bottom is 50' north.

Signature: *Jane Newstetter*

Title: Land Surveyor

Date: 10/20/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.
Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown
on the DIAGRAM, 26" in the ground.
From Which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE
Douglas Fir, 20" dia., bears N37°29'E, 69.1 ft., scribed: C-E1/16 S24 BT
Douglas Fir, 26" dia., bears S72°07'E, 43.7 ft., scribed: C-E1/16 S24 BT
Measurements to BT's taken with an Electronic Tacheometer with bearings
based on the survey control network. Set steel fence post with Land Survey
Monument (54-9) and Property Boundary (54-2) signs 5' north and south of
the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT
scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze
and Land Survey Monument (54-9) signs on back of each tree as required.
Painted a 6" red band above Bearing Trees signs.

Work Done by: Susan E. Newstetter Dr. Land Surveyor No. 2405 Date: 10/20/94
Certified Cor. Record Prepared? Yes No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. P-24

T.48., R.32E., W.M.