


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Q-13

History of original corner establishment:

None. Corner established as part of this survey.



Description of corner evidence found:

Found a Kinzua tag, W-10' more or less from cornerpoint.

Description of monument and accessories established to perpetuate the original location of this corner:

At position established by survey...

Set a 2 1/2"x30" aluminum pipe with 2 1/2" aluminum cap 24" in ground surrounded with mound of earth only and set a steel fence post East of corner and attached signs 54-2 & 54-9. Cap marked as shown in corner diagram.

New bearing trees established:

A 12" western larch brs S06° E, 29.0' scribed S1/16S22 BT.

A 18" western larch brs N76 1/2° W, 80.1' scribed S1/16S21 BT.

New BT's have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

Compass declination 18° East.

I hereby certify that the above corner monument was properly established to U.S.F.S. standards by me on June 09, 1992.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of...County Surveyor..... County of... Umatilla

State of...Oregon....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by (COUNTY OFFICIAL)

(DEPUTY) RECEIVED BY

Umatilla County Surveyor

Date 7-92

Rec'd By [Signature]

No. 72-806

Q-13