


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Q-15

History of original corner establishment:

None. Corner established as part of this survey.



Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

At position established by survey...

Set a 2 1/2"x30" aluminum pipe with 2 1/2" aluminum cap 20" in ground surrounded with mound of earth and stone set steel fence post next to corner and attached signs 54-2 & 54-9. Cap marked as shown in corner diagram.

New bearing trees established:

A 19" ponderosa pine brs N2°W, 14.4' scribed CS1/16S22 BT.

A 11" ponderosa pine brs N78 1/4°W, 66.4' scribed CS1/16S22 BT.

New BT's have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

Compass declination 18° East.

I hereby certify that the above corner monument was properly established to U.S.F.S. standards by me on June 10, 1992.

REGISTERED PROFESSIONAL LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of County Surveyor ..... County of Umatilla  
Oregon ..... I hereby certify that the within instrument was filed in this office  
for record on the ..... day of ..... , 19.....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 7-92

Rec'd. By [Signature]

No. 92-80-B

Q-15

☆ GPO-788-276