


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Q-9

History of original corner establishment:

None. Corner established as part of this survey.



Description of corner evidence found:

Found a small stone mound S 72°E, 4' from corner point.

Description of monument and accessories I established to perpetuate the original location of this corner:

At position established by survey...

Set a 2 1/2"x30" aluminum pipe with 2 1/2" aluminum cap 15" in ground to rock, surrounded with mound of earth and stone set steel fence post South of corner and attached signs 54-2 & 54-9. Cap marked as shown in corner diagram.

New bearing trees established:

A 21" ponderosa pine brs N07 1/2°W, 186.9' scribed S1/16S20 BT.

A 17" ponderosa pine brs S73 1/2°E, 249.6' scribed S1/16S21 BT.

New BT's have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

Compass declination 18° East.

I hereby certify that the above corner monument was properly established to U.S.F.S. standards by me on June 6, 1992.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of...County...Surveyor..... County of...Umatilla..... State of...Oregon....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19....

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 7-92

Rec'd By KR

No. 72-80-B

Q-9

★ OPO-798-276