

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


R-11

History of original corner establishment:

Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 390, dated May 12, 1881. Surveyor General records state: Set basalt stone 14X12X4 on slight N.W. slope for 1/4 Sec. cor. A pine 9 in. di. brs. N68°E, 44 lks. dist. A pine 10 in. di. brs. S83°W, 108 lks. dist.

Corner remonumented by Craig L. Wanless, BLM Cadastral Surveyor under instructions, dated July 18, 1977.

The 1/4 sec. cor. of secs. 21 and 28, monumented with the original unmarked basalt stone 14X12X4 ins., loosely set in a mound of stone, 2 ft. high, from which an original bearing tree: A twin pine 18 ins. diam. brs S83°W, 108 lks. dist. with scribe marks 1/4 S visible on open and burned blaze. At the corner point... Set an iron post, 28 ins. long, 2 1/2 ins. diam. 24 ins. in ground with brass cap mkd (as shown in corner diagram) from which new bearing trees: A lodgepole pine 11 ins. diam. brs N 1/2°E, 23 1/2 lks. dist. mkd 1/4 S 21 BT. A lodgepole pine 11 ins. diam. brs S60°E, 26 1/2 lks. dist. mkd 1/4 S 28 BT. Deposit corner stone alongside iron post.



Description of corner evidence found:

- Found 2 1/2" iron post with 3 1/4" brass cap (marked as shown in corner diagram) in mound of stone.
- A 13" ponderosa pine brs S61°E, 17.6' with visible scribing.
- A 20" ponderosa pine brs N82 1/2°W, 70.5' with visible scribing.
- A 12" ponderosa pine brs N1°W, 15.9' with visible scribing.

Description of monument and accessories established to perpetuate the original location of this corner:

New bearing tree established:

A 13" ponderosa pine brs S17°E, 10.2' scribed 1/4 S 28 BT.

New bearing tree has a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT. Set 6' steel fence post next to corner with sign 54-9 & 54-2 attached.

Compass declination 18° East.

I hereby certify that the above corner monument was properly maintained to U.S.F.S. standards by me on June 02, 1992.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of... County Surveyor County of... Umatilla
 State of... Oregon I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
 Umatilla County Surveyor
 Date 7-92
 Rec'd By KR
 No. 92-80-B

R-11