

USDA FOREST SERVICE  
Index

CORNER RECORD (SEARCH)

File No. R-19  
T.4S., R.32E.  
Meridian: Willamette

R.D.: N.F.J.D.  
N.F.: UMATILLA

Co. Survey No:  
County: Umatilla

CORNER DIAGRAM | DESCRIBE CORNER MONUMENT FOUND

T4S R32E | Found iron monument, in a mound of stone, with a brass  
S23 | cap marked as shown in DIAGRAM. Monument is solid and  
1/4 ——— | firm.  
S26 |  
1977 |

(BLM Cap)

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

PHOTO ID DATA

Photo No.

Filed At

Object ID

Ponderosa Pine, 12" dia., with scribing visible, bears  
N20°31'E, 29.0 ft. (BLM Rec: N21°E, 29.04 ft.) Tree is  
alive and well.

PLANE CO-ORD

State Zone

X

Y

Estab. By

Ponderosa Pine, 28" dia., with healed blaze, bears  
S19°49'W, 37.4 ft. (Org. Rec: S23°W, 40.92) Tree is  
alive and well.

DESCRIBE CORNER LOCATION:

An old E-W fence is approx. 15 ft. north.

Signature:



Title: Land Surveyor

Date: 10/17/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.  
No work is needed on the monument.  
From Which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE  
Douglas Fir, 12" dia., bears S27°45'E, 23.8 ft., scribed: 1/4 S26 BT  
5/8" x 30" rebar, set in a mound of stone, with yellow plastic cap marked  
PLS 2405 bears N40°30'W, 7.9 ft.  
Measurements to BT and rebar taken with a magnetic compass, declination 20°  
East, and a nylon clad steel tape. Set steel fence post with Land Survey  
Monument (54-9) and Property Boundary (54-2) signs 5' north and south of  
the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT  
scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze  
and Land Survey Monument (54-9) signs on back of each tree as required.  
Painted a 6" red band above Bearing Trees signs.

Work Done by: Susan E. Newstetter Or. Land Surveyor No. 2405 Date: 10/17/94  
Certified Cor. Record Prepared?  Yes  No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. R-19 T.4S., R.32E., W.M.