

INDEX No. R-20

History of original corner establishment:

None. Corner established this survey.

DIAGRAM  
T4S R32E  
S23  
E1/16—  
S26  
1994  
PLS 2405

Description of Corner Evidence Found:

None. Corner established this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 24" in the ground.

From Which:

Ponderosa Pine, 10" dia., bears N30°17'E, 7.3 ft., scribed: E1/16 S23 BT

Douglar Fir, 22" dia., bears S21°11'W, 56.3 ft., scribed: E1/16 S23 BT

Measurements to BT's taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' north and south of the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs.

REGISTERED PROFESSIONAL LAND SURVEYOR  
*Susan E. Newstetter*  
OREGON JULY 26, 1988  
SUSAN E. NEWSTETTER 2405  
Renewal Date: 12/31/96

This work was performed by:  
Susan E. Newstetter PLS 2405  
Witnessed by: Rick Saul and  
Rick Pewonka  
October 26, 1994

RECEIVED BY  
Umatilla County Surveyor  
Date: 1-95  
Rec'd By: KK  
No. 95-15-8

Office of \_\_\_\_\_ County of \_\_\_\_\_ State of \_\_\_\_\_ I hereby certify that the within instrument was filed in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_ by \_\_\_\_\_  
(COUNTY OFFICIAL) (DEPUTY) R-20