

USDA FOREST SERVICE

CORNER RECORD (SEARCH)

Index

File No. R-20

R.D.: N.F.J.D.

Co. Survey No:

T.4S., R.32E.

N.F.: UMATILLA

County: Umatilla

Meridian: Willamette

CORNER DIAGRAM

DESCRIBE CORNER MONUMENT FOUND

T4S R32E

S23

None. Corner established this survey.

E1/16—

S26

1994

PLS 2405

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None. Corner established this survey.

PHOTO ID DATA

Photo No.

Filed At

Object ID

PLANE CO-ORD

X

Y

Estab.By

DESCRIBE CORNER LOCATION:

Corner falls on east slope of P.Pine and D. Fir. N-S draw
bottom is 150 ft. east.

Signature:



Title: Land Surveyor

Date: 10/26/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.
Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown
on the DIAGRAM, 24" in the ground.

From Which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE
Ponderosa Pine, 10" dia., bears N30°17'E, 7.3 ft., scribed: E1/16 S23 BT
Douglas Fir, 22" dia., bears S21°11'W, 56.3 ft., scribed: E1/16 S26 BT
Measurements to BT's taken with an Electronic Tacheometer with bearings based on
the survey control network. Set steel fence post with Land Survey Monument
(54-9) and Property Boundary (54-2) signs 5' north and south of the monument.
Nailed a brass washer stamped PLS 2405 on blaze above BT scribe as taken this
survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument
(54-9) signs on back of each tree as required. Painted a 6" red band above
Bearing Trees signs.

Work Done by: Susan E. Newstetter Or. Land Surveyor No. 2405 Date: 10/26/94
Certified Cor. Record Prepared? Yes No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. R-20

T.4S., R.32E., W.M.