

File No. R-23  
T.4S., R.32E.  
Meridian: Willamette

R.D.: N.F.J.D.  
N.F.: UMATILLA

Co. Survey No:  
County: Umatilla

CORNER DIAGRAM

DESCRIBE CORNER MONUMENT FOUND

T4S R32E | Found iron monument, in a mound of stone, with a brass  
S24 | cap marked as shown in DIAGRAM. Monument is solid and  
1/4 ——— | firm.  
S25 |  
1977 |

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

(BLM Cap) | Ponderosa Pine snag, 24" dia., with healed blaze, bears  
PHOTO ID DATA | N17°34'E, 74.8 ft. (Orig. Rec: N16°E, 75.24 ft.)  
Photo No. | Ponderosa Pine snag, 28" dia., down w/scribing, bears  
Filed At | S59°32'E. 15.8 ft. (Orig. Rec: S58°E, 17.16 ft)  
Object ID | Ponderosa Pine, 14" dia., scribed 1/4 S25 BT, bears  
S44°13'E, 135.9 ft. (BLM Rec: S43°E, 83.82 ft)  
PLANE CO-ORD | Ponderosa Pine, 16" dia., scribed 1/4 S24 BT, bears  
State Zone | N47°25'E, 44.6 ft. (BLM Rec: N48°E, 44.88 ft.)

X |  
Y | DESCRIBE CORNER LOCATION:

Estab. By | An old E-W road is approx 350 ft. north.

Signature:



Title: Land Surveyor

Date: 10/17/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.  
No work is needed on the monument.  
From Which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE  
5/8" x 30" rebar, set approximately 28 ins. in ground, with yellow plastic  
cap marked PLS 2405 bears:

S58°45'W, 8.9 ft. (No groove on rebar)

N44°30'W, 9.8 ft. (1 groove on rebar)

Measurements to rebars taken with a magnetic compass, declination 20° East,  
and a nylon clad steel tape. Set steel fence post with Land Survey  
Monument (54-9) and Property Boundary (54-2) signs 5' north and south of  
the monument.

Work Done by: Susan E. Newstetter Dr. Land Surveyor No. 2405 Date: 10/17/94  
Certified Cor. Record Prepared?  Yes  No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. R-23

T.4S., R.32E., W.M.