

INDEX No. T-17

History of original corner establishment:

This corner was originally established George Pershin, in 1881, under GLO Contract No. 390. Surveyor General Field Notes state:

Set basalt stone 18x12x4 for 1/4 sec. cor.

DIAGRAM
 T4S R32E
 1/4
 S27|S26
 1994
 PLS 2405

Description of Corner Evidence Found:

Found 18"x12"x4" stone, marked 1/4, in the bottom of a rock jack. Accepted as the original position.

Description of monument and accessories I established to perpetuate the original location of this corner:

Moving the original corner stone aside I set in it's place a 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 14" in the ground and raised a mound of earth and stone around the monument. The original stone is alongside the monument on the north side.

From Which:

Ponderosa Pine, 12" dia., bears N64°30'E, 108.4 ft., scribed: 1/4 S26 BT

Ponderosa Pine, 16" dia., bears S52°15'E, 132.4 ft., scribed: 1/4 S26 BT

5/8"x30" rebar, with yellow plastic cap marked PLS 2405, bears:
 N47°15'W, 12.1 ft. (no grooves on rebar)
 S46°00'W, 11.9 ft. (1 groove on rebar)

Measurements to BT's and rebar taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' north of the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs.

REGISTERED PROFESSIONAL LAND SURVEYOR
Susan E. Newstetter
 OREGON
 JULY 26, 1989
 SUSAN E. NEWSTETTER
 2405
 Renewal Date: 12/31/96

This work was performed by:
 Susan E. Newstetter PLS 2405
 Witnessed by: Rick Saul and
 Rick Pewonka
 November 1, 1994

RECEIVED BY
 Umatilla County Surveyor
 Date 1-95
 Rec'd By RS
 No. 95-15-B

Office of _____ County of _____ T-17
 State of _____ I hereby certify that the within instrument was
 filed in this office for record on the _____ day of _____, 19____
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)