

## USDA FOREST SERVICE

## CORNER RECORD (SEARCH)

Index

File No. T-18

R.D.: N.F.J.D.

Co. Survey No:

T.4S., R.32E.

N.F.: UMATILLA

County: Umatilla

Meridian: Willamette

## CORNER DIAGRAM

## DESCRIBE CORNER MONUMENT FOUND

T4S R32E

W1/16

C-----C

S26

1994

PLS 2405

None. Corner established this survey.

## DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None. Corner established this survey

## PHOTO ID DATA

Photo No.

Filed At

Object ID

## PLANE CO-ORD

State Zone

X

Y

Estab.By

## DESCRIBE CORNER LOCATION:

Corner falls on gentle north slope of P.Pine.

Signature:



Title: Land Surveyor

Date: 11/2/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.  
Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown  
on the DIAGRAM, 26" in the ground.

From Which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE  
Ponderosa Pine, 12" dia., bears S05°56'E, 14.9 ft., scribed: C-W1/16 S26 BT  
Ponderosa Pine, 12" dia., bears S82°30'W, 33.3 ft., scribed: C-W1/16 S26 BT  
Measurements to BT's taken with an Electronic Tacheometer with bearings  
based on the survey control network. Set steel fence post with Land Survey  
Monument (54-9) and Property Boundary (54-2) signs 5' south and west of the  
monument. Nailed a brass washer stamped FLS 2405 on blaze above BT scribe  
as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and  
Land Survey Monument (54-9) signs on back of each tree as required.  
Painted a 6" red band above Bearing Trees signs.

Work Done by: Susan E. Newstetter Dr. Land Surveyor No. 2405 Date: 11/2/94  
Certified Cor. Record Prepared?  Yes  No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. T-18

T.4S., R.32E., W.M.