

INDEX No. T-19

History of original corner establishment:

None. Corner established this survey.

DIAGRAM  
T4S R32E  
C1/4  
•  
S26  
1994  
PLS 2405

Description of Corner Evidence Found:

None. Corner established this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 26" in the ground.

From Which:

- Ponderosa Pine, 10" dia., bears N70°22'E, 66.0 ft., scribed: C1/4 S26 BT
- Ponderosa Pine, 9" dia., bears S66°56'E, 34.1 ft., scribed: C1/4 S26 BT
- Ponderosa Pine, 9" dia., bears S04°07'W, 67.8 ft., scribed: C1/4 S26 BT
- Ponderosa Pine, 14" dia., bears S59°36'W, 42.1 ft., scribed: C1/4 S26 BT

Measurements to BT's taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) sign 5' north of the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Susan E. Newstetter*

OREGON  
JULY 26, 1930  
SUSAN E. NEWSTETTER  
2405

Renewal Date: 12/31/96

This work was performed by:  
Susan E. Newstetter PLS 2405  
Witnessed by: Rick Saul and  
Rick Pewonka  
November 2, 1994

RECEIVED BY

Umatilla County Surveyor  
Date 1-95  
Rec'd By JK  
No. 95-15-B

Office of \_\_\_\_\_ County of T-19  
State of \_\_\_\_\_ I hereby certify that the within instrument was  
filed in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_  
\_\_\_\_\_ by \_\_\_\_\_  
(COUNTY OFFICIAL) (DEPUTY)