

INDEX No. T-23

History of original corner establishment:

None. Corner established this survey.

DIAGRAM  
T4S R32E  
C1/4  
•  
S25  
1994  
PLS 2405

Description of Corner Evidence Found:

None. Corner established this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 26" in the ground.

From Which:

Lodgepole pine, 9" dia., bears N52°15'W, 36.9 ft., scribed: C1/4 S25 BT

Western Larch, 20" dia., bears S71°30'E, 72.7 ft., scribed: C1/4 S25 BT

5/8"x30" rebar, set 28" in ground, with yellow plastic cap marked PLS 2405 bears:

N38°30'E, 6.5 ft. (1 groove on rebar)  
S37°45'W, 9.7 ft. (no groove on rebar)

Measurements to BT's and rebar taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' north and east of the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs.

REGISTERED PROFESSIONAL LAND SURVEYOR  
*Susan E. Newstetter*  
OREGON JULY 29, 1980  
SUSAN E. NEWSTETTER  
2405  
Renewal Date: 12/31/96

This work was performed by:  
Susan E. Newstetter PLS 2405  
Witnessed by: Rick Saul and  
Rick Pewonka  
October 24, 1994

RECEIVED BY  
Umatilla County Surveyor  
Date 1-95  
Rec'd By KK  
No. 95-15-B

Office of \_\_\_\_\_ County of \_\_\_\_\_  
State of \_\_\_\_\_ I hereby certify that the within instrument was  
filed in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_  
\_\_\_\_\_  
(COUNTY OFFICIAL) by \_\_\_\_\_ (DEPUTY)

T-23