

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. T-24

History of original corner establishment:

None. Corner established this survey.

DIAGRAM  
T4S R32E  
E1/16  
C-----C  
S25  
1994  
PLS 2405

Description of Corner Evidence Found:

None. Corner established this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 26" in the ground.

From Which:

Western Larch, 24" dia., bears N81°30'E, 43.6 ft., scribed: C-E1/16 S25 BT

White Fir, 11" dia., bears S48°00'W, 18.9 ft., scribed: C-E1/16 S25 BT

Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' south and west of the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Susan E. Newstetter*

OREGON  
JULY 26, 1989  
SUSAN E. NEWSTETTER  
2405

Renewal Date: 12/31/96

This work was performed by:  
Susan E. Newstetter PLS 2405  
Witnessed by: Rick Saul and  
Rick Pewonka  
October 24, 1994

RECEIVED BY

Umatilla County Surveyor

Date 1-95

Rec'd By KK

No. 95-15-B

Office of \_\_\_\_\_ County of \_\_\_\_\_  
State of \_\_\_\_\_ I hereby certify that the within instrument was  
filed in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_  
\_\_\_\_\_ by \_\_\_\_\_

(COUNTY OFFICIAL)

(DEPUTY)

T-24