

INDEX No. V-15

History of original corner establishment:

This corner was originally established George Pershin, in 1881, under GLO Contract No. 390. Surveyor General Field Notes state:

DIAGRAM
 T4S R32E
 S27
 1/4 —
 S34
 1977

Set basalt stone 14x12x4 in. in ravine for 1/4 sec. cor.

(BLM Cap)

A pine 6 in. dia. brs. N47°E, 86 lks. dist.
 A pine 20 in. dia. brs. S23°W, 177 lks dist.

In 1977 the Bureau of Land Management (BLM) conducted a remonumentation of certain original corner points in T.4S., R.32E., W.M., under Special Instructions dated May 3, 1957, Group 350. Their record states:

The 1/4 sec. cor. of secs. 27 and 34, monumented with the original unmarked basalt stone, 14x12x4 ins., firmly set 4 ins. in the ground, and in a mound of stone, 3 ft. base, 6 ins. high, from which the original bearing trees: A pine, 23 ins. diam., bears N47°E, 86 lks. dist., with healed blaze. A pine, 22 ins. diam., bears S23°W, 177 lks. dist., with scribe marks 1/4 S visible on open blaze. At the corner point set an iron post, 28 ins. long, 2 1/2 ins. diam., 22 ins. in the ground, and in a mound of stone, 3 ft. base, to top, with brass cap mkd. (SEE DIAGRAM). Deposit corner stone alongside iron post. Corner is located 15 lks. east of dirt road, 12 lks wide, bears N and E.

Description of Corner Evidence Found:

Found iron monument pushed over after recent logging operation.

Ponderosa Pine stump, 26" dia., with healed blaze, bears N46°38'E, 54.0 ft. (Orig. Rec: N47°E, 56.76 ft)

Ponderosa Pine, 22" dia., with scribing visible, bears S22°35'W, 116.3 ft. (Orig. Rec: S23°W, 116.82 ft)

Description of monument and accessories I established to perpetuate the original location of this corner:

Reset the BLM monument back in it's original hole and raised a mound of stones around the monument.

From Which:

5/8" x 30" rebar with yellow plastic cap marked PLS 2405 bears:

- N45°W, 10.0 ft. (no grooves on rebar)
- N45°E, 10.0 ft. (1 groove on rebar)
- S45°E, 10.0 ft. (2 grooves on rebar)
- S45°W, 10.0 ft. (3 grooves on rebar)

Measurements to rebars taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) sign 5' north of the monument.

This work was performed by:
 Susan E. Newstetter PLS 2405
 Witnessed by: Rick Saul and
 Rick Pewonka
 October 17, 1994



Renewal Date: 12/31/96

RECEIVED BY
 Umatilla County Surveyors
 Date 1-95
 Rec'd By RS
 No. 95-15-B

Office of _____ County of _____ **V-15**
 State of _____ I hereby certify that the within instrument was
 filed in this office for record on the _____ day of _____, 19____
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)