

USDA FOREST SERVICE

CORNER RECORD (SEARCH)

Index

File No. V-18

R.D.: N.F.J.D.

Co. Survey No:

T.4S., R.32E.

N.F.: UMATILLA

County: Umatilla

Meridian: Willamette

CORNER DIAGRAM | DESCRIBE CORNER MONUMENT FOUND

T4S R32E |

S26 |

None. Corner established this survey.

W1/16 |

S35 |

1994 |

PLS 2405 |

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None. Corner established this survey.

PHOTO ID DATA |

Photo No. |

Filed At |

Object ID |

PLANE CO-ORD |

State Zone |

X |

Y | DESCRIBE CORNER LOCATION:

Estab.By |

Corner falls on slight south slope of P.Pine. E-W fence is 1 ft. south.

Signature: *Sue Newstetter*

Title: Land Surveyor

Date: 11/1/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.
Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown
on the DIAGRAM, 10" in the ground and raised a mound of stone, 2 1/2 ft. dia.
x 1 1/2 ft. dia. around the monument. From Which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE
Ponderosa Pine, 18" dia., bears N47°16'W, 63.2 ft., scribed: W1/16 S26 BT
5/8" x 30" iron pin, set approx 24 ins. in the ground, with yellow plastic
cap marked PLS 2405 bears:
S38°15'W, 9.8 ft.

Measurements to BT and rebar taken with an Electronic Tacheometer with
bearings based on the survey control network. Set steel fence post with
Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' north of
the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT
scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze
and Land Survey Monument (54-9) signs on back of each tree as required.
Painted a 6" red band above Bearing Trees signs.

Work Done by: Susan E. Newstetter Or. Land Surveyor No. 2405 Date: 11/1/94
Certified Cor. Record Prepared? Yes No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. V-18

T.4S., R.3E., W.M.