


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. C-17

History of original corner establishment:

In 1881, under GLO Contract No. 410, George S. Pershin set a stone 16x8x7, from which a 12" Pine bears N77°E, 126 lks.



Description of corner evidence found:

No corner monument found.

Found a 12 1/2" P. Pine bearing N77°E, 83.2 ft., blaze visible, scribing faint.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 2 1/2" Brass cap in concrete 6" below ground, stamped:

New BT's:

- An 8 1/2" Fir bears S 24 1/2°W, 111.6 ft., scribed 1/4 S3 BT.
- A 9" W. Larch bears S46 1/4°E, 93.8 ft., scribed 1/4 S2 BT.

T4S R33E
 1/4
 S3-S2
 RLS 1848
 1984

Painted blazes and attached signs as per Standard Specifications for Cadastral Surveys, USFS Region 6, March 1982.

Set a metal fence post S6°W, 32 ft.

Compass Declination: 19 1/2°E
Witness: G. Arrand

From 2110, go north on 2110-220 .2 mi. Corner is on the right hand side of the road, 10 ft. from the road.

I hereby certify the above described corner monument and/or accessories was established as described on June 8, 1984.



Office of Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 10th day of July, 1984
David Kaumben by Betty Cochran
 (COUNTY OFFICIAL) (DEPUTY)

C-17