


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. J-21

History of original corner establishment:

In 1881, under Glo Contract No. 410, George S. Pershin set a stone 18x12x5, from which a 10" Pine bears N34°E, 31 lks.; a 10" Pine bears S44°E, 11 lks.; and a 12" Tamarack bears S3°W, 34 lks.



Description of corner evidence found:

Found original stone.

Bearing Tree's Found:

A 16" L. Pine bearing N34°E, 20.7 ft., original blaze visible.  
S13 BT dead and down. Stump hole bearing S65°E, 7.5 ft., scribed "T4S R33E S13 BT".

Description of monument and accessories established to perpetuate the original location of this corner:


Set a 2 1/2"x30" aluminum capped aluminum pipe rising 7", stamped:

Set original stone along north side in hole.

T4S                  R33E

New BT's:

- A 7 1/2" W. Larch bearing N59.5°W, 68.4 ft., scribed T4S R33E S11 BT
- A 2 1/2" Spruce bearing N40°E, 28.7 ft., scribed " 'x' BT".
- A 9" W. Larch bearing S65°E, 37.0 ft., scribed "T4S R33E S13 BT".
- A 5" W. Larch bearing S40°W, 9.0 ft., scribed "T4S R33E S14 BT".



Painted blazes and attached signs as per Standard Specifications for Cadastral Surveys, USFS Region 6, March, 1982. Set metal fence post 4 ft. north of corner.

Compass Declination: 19 1/2° E

Witness: D. Scott

From 2110, take 5435 west .5 mi. to an unnumbered rd. to the right. Follow northerly till the rd. turn west. There is a rd going north; follow it to the end (1/4 mi. Corner is 50 ft. north of the no. edge of the clearing on the edge of a swamp.

I hereby certify the above described corner monument and/or accessories was established as described on May 11, 1984.

Office of Washburn County of Washburn

State of Oregon, I hereby certify that the within instrument was filed in this office

for record on the 10<sup>th</sup> day of July, 1984

Daniel Washburn by Betty Cochran

(COUNTY OFFICIAL)

(DEPUTY)

