CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1881 by George S. Pershin as follows: 21 | 22

At 80.00 chains north of section corner 28 27, set a basalt

stone 16"x12"x8", 11" in ground marked with 3 notches on South and 3 notches on East edges, from which:

A Tamarack, 8" dia. brs. N28°E, 43 1ks (28.4 ft.) marked T4S, R33E, S15, BT.

A Tamarack, 10" dia. brs. S38°E, 113 1ks (74.6 ft.) marked

T4S, R33E, S22, BT. A Tamarack, 10" dia. brs. S53°W, 73 1ks (48.2 ft.) marked T4S, R33E, S21, BT.

A Pine, 6" dia. brs. N430W, 23 1ks (15.2 ft.) marked T4S, R33E, S16, BT.

Description of corner evidence found:

From the corner position, which is in Road No. 54, I find the following original corner evidence:

A decayed tamarack log lying on the ground with an axe face and fragmentary scribing. Root hole where this tree stood bears S53°W, 48.2 ft.

A root hole, with a badly decayed tamarack log lying alongside, bears S38°E, 74.6 feet. No scribes or marks remain. Location of the original NE & NW bearing trees falls in the roadway.

I also find the following evidence of perpetuation efforts, not of record: A location tag, on a lodgepole pine, is marked "W29' to COR, '63 T. Holden". This tag bears S83°E, 30.6 ft. from corner. A location tag on the ground on edge of root hole of SW BT is dated 1944.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the corner point, as determined from the original evidence, I set a 2"x24" iron rod. The top of the rod is 6" below the road surface. From which bears:

A 2½"x30" galvanized iron pipe with a 3" brass cap attached. The iron pipe is

set 26" into the ground. The brass cap is marked: W.C. This witness corner bears East, 40.0 ft. from T4S R33E S16 | S15 the section corner.

A 15" larch bears S89° 30'E, 45.5 ft. scribed S21 S22 "T4S, R33E, S22, BT" on double blazes. A 13" Douglas-fir bears S71°W, 49.3 ft. scribed PLS 1636 1981

"T4S, R33E, S21, BT" on double blazes.

A 12" Douglas-fir bears N62°W, 41.6 ft. scribed

"T4S, R33E, S16, BT" on double blazes. A 23" ponderosa pine bears N32°E, 126.5 ft. scribed "T4S, R33E, S15, BT" on double blazes. De: 20° East.

54-3 and 54-4 signs were placed on all four new bearing trees.

I hereby certify the above corner location was perpetuated as hereon described on October 28, 1981. Witness: John T. Hall.

OREGON Durveyer County of Bratilla DENNIS L. GAYLORD State of Oregon

(COUNTY OFFICIAL) Dy Backy Shift

(DEPUTY)

RECEIVED BY

Form R6-7100-57 (9/71)

Umatilla County Surveyor

REGISTERED PROFESSIONAL AND SURVEYS

DIAGRAM

T4S R33E

S16 | S15

S21 | S22

N-13