

USDA FOREST SERVICE

CORNER RECORD (SEARCH)

Index

File No. P-25

R.D.: N.F.J.D.

Co. Survey No:

T.4S., R.32E.

N.F.: UMATILLA

County: Umatilla

Meridian: Willamette

CORNER DIAGRAM : DESCRIBE CORNER MONUMENT FOUND

T4S | None. Found several stones of near record size
1/4 | 18x12x5, however no marks. The search area fell on
R32E R33E | the west bank of stream. Looked on both sides, nothing
S241S19 | found.

1994
PLS 2405 | DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None. Old logging in the area and I believe they were
lost to this logging.

PHOTO ID DATA
Photo No. |
Filed At |
Object ID |

PLANE CO-ORD
State Zone |
X |
Y |

DESCRIBE CORNER LOCATION:
Estab.By | Corner falls in N-S draw bottom of spruce and W.Larch.
N-S stream is 3' east. Fork in stream is 130' north.

Signature: *Aue Newstetter* Title: Land Surveyor Date: 10/21/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.
Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown
on the DIAGRAM, 18" in the ground and raised a mound of stone around the
monument. From Which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE
Western Larch, 20" dia., bears N36°16'W, 87.0 ft., scribed: 1/4 S24 BT
Spruce, 14" dia., bears N38°57'E, 37.1 ft., scribed: 1/4 S19 BT
Western Larch, 28" dia., bears S81°52'E, 37.6 ft., scribed: 1/4 S19 BT
Spruce, 24" dia., bears S55°24'W, 63.8 ft., scribed: 1/4 S24 BT
Measurements to BT's taken with an Electronic Tacheometer with bearings
based on the survey control network. Set steel fence post with Land Survey
Monument (54-9) sign 5' north of the monument. Nailed a brass washer
stamped PLS 2405 on blaze above BT scribe as taken this survey. Nailed
Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs
on back of each tree as required. Painted a 6" red band above Bearing
Trees signs.

Work Done by: Susan E. Newstetter Dr. Land Surveyor No. 2405 Date: 10/21/94
Certified Cor. Record Prepared? Yes No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. P-25

T.4S., R.32E., W.M.