

History of original corner establishment:

This corner was originally established George Pershin, in 1881, under GLO Contract No. 390. Surveyor General Field Notes state:

DIAGRAM
T4S
R32E R33E
S24|S19
S25|S30
1977
(BLM Cap)

Set basalt stone 18x10x4 on level for cor. to secs. 24 x 25 x 19 & 30.

- A Pine 20 in. dia. brs N24°E, 155 lks. dist.
- A Pine 8 in. dia. brs S 7°E, 105 lks. dist.
- A Pine 10 in. dia. brs S27°W, 74 lks. dist.
- A Pine 9 in. dia. brs N28°W, 87 lks. dist.

In 1977 the Bureau of Land Management (BLM) conducted a remonumentation of certain original corner points in T.4S., R.32E., W.M., under Special Instructions dated May 3, 1957, Group 350. Their record states:

The cor. of secs. 19,24,25 and 30, on the E. bdy. of the tp., monumented with the original unmarked basalt stone, 24x18x4 ins. (record 18x10x4 ins.) firmly set 6 ins. in the ground, and in a mound of stone, 4 ft. base, 1 ft. high, from which the remains of the original bearing trees: A root hole, bears N24°E, 135 lks. dist., with a down pine alongside, size indeterminate, no marks visible on open blaze. A decayed pine stump, size indeterminate, bears S7°E, 112 lks. dist., no marks visible, (Record 105 lks). A pine, 20 ins. diam., bears S32°W, 74 lks. dist., no marks visible on open blaze. (Record, S27°W) A pine, 24 ins. diam., bears N26°W, 87 lks. dist., with scribe marks T4S R visible on open blaze. (Record N28°W). At the corner point set an iron post, 28 ins. long, 2 1/2 ins. diam., 10 ins. in the ground, to solid rock, and in a mound of stone 3 ft. base, to top, with brass cap marked (SEE DIAGRAM) from which new bearing trees: A lodgepole pine, 9 ins. diam., bears N49 1/2°E, 35 1/2 lks. dist., mkd. T4S R33E S19 BT. A lodgepole pine, 8 ins. diam., bears S36°E, 82 1/2 lks. dist., mkd. T4S R33E S30 BT. A lodgepole pine, 8 ins. diam., bears N33 1/2°W, 47 lks. dist., mkd. T4S R32E S24 BT.

Description of Corner Evidence Found:

Found iron monument, in a mound of stone, with a brass cap marked as shown in DIAGRAM. Monument is solid and firm.

- Ponderosa Pine, 26" dia., with scribing visible, bears N27°50'W, 56.3 ft. (Org. Rec: N28°W, 87 lks; BLM Rec: N26°W, 87 lks.)
- Ponderosa Pine, 22" dia., healed blaze chopped on with no scribing visible, bears S30°58'W, 48.4 ft. (Org. Rec. S27°W, 48.84 ft. BLM Rec: S32°W, 48.84 ft.)
- Ponderosa Pine, 10" dia., with scribing visible, bears N34°58'W, 31.3 ft. (BLM Rec: N33 1/2°W, 31.02 ft.)
- Ponderosa Pine, 9" dia., down scribing visible, bears S37°30'E, 54.3 ft. (BLM Rec: S36°E, 54.45 ft)
- Ponderosa Pine, 9" dia., down scribing visible, bears N47°13'E, 23.2 ft. (BLM Rec: N49 1/2°E, 23.43 ft.)

Description of monument and accessories I established to perpetuate the original location of this corner:

No work is needed on the monument.
From Which:

- Ponderosa Pine, 12" dia, bears N26°15'E, 74.3 ft., scribed: T4S R33E S19 BT
- Ponderosa Pine, 10" dia, bears S12°00'E, 48.7 ft., scribed: T4S R33E S30 BT
- Ponderosa Pine, 10" dia, bears S03°30'W, 38.8 ft., scribed: T4S R32E S25 BT

Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) sign 5' south of the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs.

REGISTERED PROFESSIONAL LAND SURVEYOR

Susan E. Newstetter

OREGON JULY 26, 1989 SUSAN E. NEWSTETTER 2405

Renewal Date: 12/31/96

This work was performed by: Susan E. Newstetter PLS 2405 Witnessed by: Rick Saul and Rick Pewonka October 17, 1994

RECEIVED BY
Umatilla County Survey
Date 1-95
Rec'd By RK
No. 95-158

R-25

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was
filed in this office for record on the _____ day of _____, 19____
by _____