


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by George S. Pershin under G.L.O. #410 in May 1881.

Set a basalt stone 16" x 12" x 8" set 11" in ground. Marked "X" on North face from which a 8" dia. Pine bears N 72°W, 68 links marked ¼ S BT. A 8" dia. Pine bears S 36°W, 63 links marked ¼ S BT.



V-19

Description of corner evidence found:

None

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½" Brass Cap on a 2½" x 30" Galvanized pipe set 15" in ground marked as shown:

Raised rock mound 2 feet in dia. from which:


A 12" Ponderosa Pine bears S 69°45'W 37.70 feet scribed ¼ S 35 BT
A 14" Ponderosa Pine bears N 68°45'W 42.60 feet scribed ¼ S 26 BT

Blazes are painted red, trees have a red band painted around them and signs number 54-3, 54-4 and Brass Washers stamped PLS 933 nailed to them.

Bearings were run with a staff compass set at a declination of 19°30'E distances were measured with a steel tape to the center of the tree.

March 1984

Witness: Rod PUNCHES
Brent Reynolds



Office of... County Surveyor County of... Umatilla
 State of... Oregon I hereby certify that the within instrument was filed in this office
 for record on the 26th day of November 1984
 by Betty Ochman (DEPUTY)