

USDA-FOREST SERVICE

Index

File No. 2-19

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. _____

Cor.

No. 14

T 45 R. 33E

R.D. Ukiah

County Umatilla

Merid. Willamette

N.F. Umatilla

State Oregon

CORNER DIAGRAM

T45 R33E



$\frac{1}{4}$ $\frac{535}{52 T55}$

DESCRIBE CORNER MONUMENT FOUND

None

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From jct. of Ukiah-Hilgard Highway and Forest Road 54 go East 1.3 mi, park and walk South 500 feet to corner.

Signature
David H Klein

Title PLS 933

Division

Headquarters


Date
7-1983

7100-52-(3,68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2 1/2" dia Brass Cap on a 2 1/2" dia. x 30" galvanized pipe
set 23" in the ground marked:



ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A 21" dia Ponderosa Pine bears N23°30'E, 111.50 feet scribed T45 R33E 1/4 535 BT
A 22" dia Ponderosa Pine bears S19°30'E, 245.5 feet scribed T55, R33E 1/4 52 BT
Blazes are painted red and have red bands around them.
Trees have signs numbers 54-3, 54-4 + Brass Washers stamped PLS
933 nailed to them.

Work Done By D. Keumbein Title Surveyor Date 7-1983 State Registration No. PLS 933
or Agency

Certified Cor. Record Prepared? Yes No Filed At: Umatilla County Date 7-1983

REMARKS

Index File No: 2-19 T. 45 R. 33 E M. Willamette Tract or Surv. No. Cor. 1/4