


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by Rufus S. Moore under General Land Office Contract No. 451. Surveror General Records state:



Set basalt stone 15 X 12 X 8 ins. for 1/4 sec. cor. from which:

- A Pine 4 ins. dia. bears S 70° W, 30 lks. dist.
- A Pine 10 ins. dia. bears N 65° E, 96 lks. dist.

No record of subsequent remonumentation was found in county records.

Description of corner evidence found:

None


(See map of Survey, dated December, 1975)

Description of monument and accessories established to perpetuate the original location of this corner

At proportionate distance I set 2 1/2" X 30" iron pipe with brass cap marked as shown 16" in ground, from which:

- A 13" Pine bears N 26° E, 88.5 ft. marked 1/4 S36 BT.
- A 16" Pine bears S 60° W, 205.2 ft. marked 1/4 S35 BT.

Raised mound of stone 5 ft. base to top of cap.
Set steel fence post 5+ ft. South.



REGISTERED
PROFESSIONAL
LAND SURVEYOR

Duane I. Griffith

OREGON
JULY 10, 18-14
DUANE I. GRIFFITH
644

Brass Washer nailed to BT blazes.
Used steel tape and magnetic compass
with 19° 30' East declination.
Measured to center of all BTs.

Office of..... County of.....
State of....., I hereby certify that the within Instrument was filed in this office
for record on the day of.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

x-21