


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by Rufus S. Moore under General Land Office Contract No. 451. Surveror General Records state: Set basalt stone 12 X 10 X 8 ins. for 1/4 sec cor. Dug pits.



No record of subsequent remonumentation was found in county records.


Description of corner evidence found:

None

(See map of Survey, dated December, 1975)

Description of monument and accessories established to perpetuate the original location of this corner

At proportionate distance I set 2 1/2" X 30" iron pipe with brass cap marked as shown 16" in ground. There are no trees or bearing objects within 1000 ft. of cor. Raised mound of stone 6 ft. base 3 ft. high. Set steel fence post 5+ ft. East.



REGISTERED PROFESSIONAL LAND SURVEYOR

Handwritten signature

OREGON JULY 10, 1964 DUANE I. GRIFFITH 644

Brass Washer nailed to BT blazes. Used steel tape and magnetic compass with 19° 30' East declination. Measured to center of all BTs.

Office of..... County of..... State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of..... by..... (COUNTY OFFICIAL) (DEPUTY)

2-23