

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: February 1998

CORNER DESIGNATION: L-17, East 1/4 Corner Section 15, T5N., R28E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by Timothy W. Davenport, under contract No. 101, dated August 5, 1861. Notes state: Set 1/4 Sec. post, in mound, with charred stake, as per instructions. Re-established by Verl R. Fraley, Umatilla County Survey Record #Q-761-A, dated 1948. Field notes state: I set an iron pin to mark the 1/4 corner of the East side of Section 15. Re-established by G. Dennis Edwards, Umatilla County Survey #88-45-C, dated August 8, 1988. Set a 1" x 30" iron pin with brass cap. New accessories: A railroad tie fence post bears S 50°33' W, 14.25 feet. A railroad tie fence post bears N 74°38' W, 11.90 feet.

MONUMENT AND ACCESSORIES FOUND:

Found a 2 3/8" brass cap on 1" iron pipe, 2" above ground, marked as shown in "Monument Marking Detail".

Existing Accessory: An aluminum tag stamped #951, in face of a railroad tie fence post bears N 75° W, 11.90 feet.

MONUMENT MARKING DETAIL:

T5N R28E
1/4
S15 · S14
1988
LS 951

MONUMENT SET:

New Accessories:

A 5/8" x 30" iron rod with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", set flush with ground bears N 80° E, 34.77 feet.

A brass washer stamped "PLS 1106" in West face of a railroad tie 1.0 foot above ground bears S 76° E, 84.20 feet.

A brass washer stamped "PLS 1106" in North face of a railroad tie 1.8 feet above ground bears S 07° W, 105.53 feet.

All accessories have bearing object tags attached.

A steel fence post with witness sign attached 2.0 feet South of corner.

LOCATION AND COMMENTS:

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells
Benjamin Weinke

Oregon State Plane Coordinate, North Zone, NAD 83(91), Int. Feet:

North: 822192.70

East: 8510953.48

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98

98-101-C