

OREGON CORNER RESTORATION FORM

Section 15 Township 5N Range 28E

N-13

County UMATILLA Date 11/95

CORNER DESIGNATION

S W Cor

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out


Previous Renewals/Surveys, etc. ORIG. SUR. BY DAVENPORT in 1861 Contat #101
DEPENDENT SURVEY BY ME IN 1988 Co Contat 1987-1

Monument(s) & Accessories Found: (Condition and Source)

NOTHING FOUND

Monument Detail

Sketch



Monument Set (Procedures and Description)

By Retracing my 1988 survey I set a
1" x 30" I. Pipe with a 2 3/8" Brass Cap stamped
as above

SEE MY SURVEY FOR COLUCCIO

New Accessories

<u>An Alum Tag #951 in P. POLE</u>	<u>Bears</u>	<u>503° 34' 40" E</u>	<u>336.70 FT.</u>
<u>" " " " " "</u>	<u>"</u>	<u>N 82° 57' 40" E</u>	<u>18.41 FT.</u>
<u>" " " " " "</u>	<u>"</u>	<u>N 4° 03' 30" E</u>	<u>262.89 FT.</u>
<u>A 5/8" x 30" rebar with 2" Alum Cap</u>	<u>"</u>	<u>WEST</u>	<u>20.00 FT</u>

Location & Comments

From Intersection of Compass Declination
US Hwy # 730 with Firm/Agency EDWARDS
LIND RD. go south SURVEYING
on LIND RD 0.67 mi. E Address P.O. BOX 763
HERMISTON, OR 97838
Party Chief D. Edwards
Notes
Witness J. Coppock

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/95

09-40-A