

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: February 1998

CORNER DESIGNATION: N-17, Northeast Corner Section 22, Township 5 North, Range 28 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by Timothy W. Davenport, under Contract No. 101, dated August 5, 1861. Notes state: Set post Cor. to Sec.s 14, 15, 22 & 23; made mound and drove charred stake, as per instructions. Recovered by G. Dennis Edwards, Umatilla County Survey No. 88-45-C, dated August 1988, notes state: Found brass cap in concrete U.S. No date. 1959?

MONUMENT AND ACCESSORIES FOUND: Found 3 1/2" brass cap in a 8" circular concrete post, 4" above ground.

Existing Accessories:

An aluminum tag stamped #951 in West face of a 6" square fence post bears N 90° E, 4.75 feet.

An aluminum tag stamped #951 in East face of a railroad tie bears N 90° W, 15.82 feet.

MONUMENT MARKING DETAIL:

U.S. ENGINEER DEPARTMENT

PORTLAND DISTRICT

T5N

R28E

15 | 14

22 | 23

BOUNDARY MONUMENT

MONUMENT SET:

New Accessories:

A brass washer stamped "PLS 1106" 1.0 foot above ground in North face of a railroad tie bears S 44° E, 49.21 feet.

The farthest North corner of a standing concrete head gate wall 2.2 feet tall bears S 71° W, 130.42 feet.

All accessories have bearing object tags attached.

A 4" x 4" post, 2.0 feet North of corner monument, with witness post sign attached.

LOCATION AND COMMENTS:

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells

Benjamin Weinke

Oregon State PLane Coordinates, North Zone, NAD 83(91), Int. Feet:

North: 819500.01

East: 8511023.60

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Remains 6-30-98

98-101-C