

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: February 1998

CORNER DESIGNATION: N-7, North 1/4 Corner Section 20, Township 5 North, Range 28 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by Timothy W. Davenport, under Contract No. 101, dated August 5, 1861. Notes state: Set 1/4 Sec. post; made mound and drove charred stake, as per instructions. Dependent Resurvey by Frank A. Tuers, under Special Instructions dated April 11, 1975 under Group Number 864. Notes state: Set an iron post, 28 ins. long, 2 1/2 ins. diam., 21 ins. in the ground, with brass cap marked as shown in "Monument Marking Detail". From which a power pole, 17 ins. dia., bears S. 53° W., 30 1/2 lks. dist., with aluminum tag mkd: JH Baxter DEPH 9 74 1-65 The Dalles, Ore. Maintained by G. Dennis Edwards, Umatilla County Survey Records #91-01-B, dated January 1991. Record states: Found a 3 1/4" BLM Brass Cap on a 2 1/2" OD Galv. Pipe 0.5 ft above surface of ground, stamped as shown in "Monument Marking Detail". New Accessories: A steel fence post w/a Bearing Object & Witness sign attached N 87°06'50" E, 2.07 feet. A steel fence post w/ a Bearing Object, Witness sign attached S 26°27'50" E 0.79 feet. A power pole w/ an Alum. Tag #951 & Bearing Object sign attached. S 42°22'30" W 12.57 feet. To Alum. Tag. A power pole w/ an Alum. Tag #951 & Bearing Object sign attached, S 52°08'50" W 19.00 feet. To Alum. Tag.

**MONUMENT AND ACCESSORIES FOUND:**

Found a 3 1/4" brass cap on 2 1/2" iron pipe, 6" above ground stamped as shown in "Monument Marking Detail".

**Existing Accessories:**

A steel fence post bears N 87° E, 2.07 feet.

A steel fence post bears S 26° E, 0.79 feet.

An aluminum tag stamped #951 in UECA pole #174000 bears S 52°09' W, 19.00 feet.

An aluminum tag stamped #951 in UECA pole #174002 bears N 42°22' W, 12.57 feet.

**MONUMENT MARKING DETAIL:**

U.S. DEPT. OF THE INTERIOR

T5N R28E

1 S17

4 S20

1975

CADASTRAL SURVEY

BUR. OF LAND MANAGEMENT

**MONUMENT SET:**

All accessories have bearing object tags attached.

Both UECA poles have witness signs attached.

**LOCATION AND COMMENTS:**

The punch mark in the cap is not centered. Tied the punch mark, it is approximately 0.02 feet North and 0.04 feet West of the Center of the cap. The distance for the existing bearing object tags are measured from the center of the cap.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells  
Benjamin Weinke

Oregon State Plane Coordinates, North Zone, NAD 83(91), Int. Feet:

North: 819310.13

East: 8497719.82

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

Will R. Wells  
OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

98-101-C

Renews 6-30-98