

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: February 1998

CORNER DESIGNATION: P-5, East Quarter Corner Section 19, Township 5 North, Range 28 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by Timothy W. Davenport, under Contract No. 101, dated August 5, 1861. Notes state: Set 1/4 Sec. Cor. post; made mound and drove charred stake, etc. Re-established by G. Dennis Edwards, Umatilla County Survey Record #91-01-B, dated January 1991. Record states: No evidence found. Set by single proportion a 1" x 30" Iron pipe with a 2 3/8" Brass Cap 0.20 ft. above surface of ground and stamped as shown in "Monument Marking Detail". Accessories: A steel fence post w/Bearing Object, Witness signs attached North 2 feet. A steel fence post w/Bearing Object, Witness signs attached, South 2 feet. A R/R tie w/Alum. Tag #951 & Bearing Object sign N 00°24'00" E, 87.72 feet. Dist. to Alum. Tag. A 3" OD Iron pipe 3 ft. high, set in conc. over H20 line w/Bearing Object sign attached. S 01°25'30" E 289.46 feet.

MONUMENT AND ACCESSORIES FOUND:

Found a 2 3/8" brass cap on 1" iron pipe, 3" above ground in fence stamped as shown in "Monument Marking Detail".

Existing Accessories:

An aluminum tag stamped #951 in face of railroad tie bears N 00°24'00" E, 87.72 feet. A 3" iron pipe, 3.0 feet above ground, bears S 01°25'30" E, 289.46 feet.

MONUMENT MARKING DETAIL:

T5N R28E
1/4
19 | 20
1990
LS 951

MONUMENT SET:

New Accessories:

A 5/8" x 30" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372", 12 inches below ground, bears S 34° W, 27.15 feet.

A 5/8" x 30" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372", 12 inches below ground, bears N 54° W, 27.15 feet.

All accessories have bearing object signs attached.

Corner has steel fence post with witness post sign attached, 1.5 feet South.

LOCATION AND COMMENTS: South at water tank by cemetery, follow dirt road along fence (South) to corner.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells
Benjamin Weinke

Oregon State Plane Coordinates, North Zone, NAD 83(91), Int. Feet:

North: 816632.20
East: 8495118.45

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-96

98-101-C