

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: February 1998

CORNER DESIGNATION: R-13, The Northeast Corner of Section 28, Township 5 North, Range 28 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by Timothy W. Davenport, under Contract No. 101, dated August 5, 1861. Notes state: Set post Cor. to Secs. 21, 22, 27 & 28. Re-established by G. Dennis Edwards, Umatilla County Survey Records #L-59-B, dated 1976. Record states: Set 5/8" rebar. Remonumented by G. Dennis Edwards, Umatilla County Survey Records #88-45-C, dated 1987. Record states: Set 1 inch x 30 inch iron pipe with brass cap.

MONUMENT AND ACCESSORIES FOUND: Found 2 1/2" brass cap buried 4" below ground surface, stamped as shown in "Monument Marking Detail".

Existing Accessories:

- An aluminum tag stamped #951 in face of a UECA pole bears N 19°55' E, 80.27 feet.
- An aluminum tag stamped #951 in face of a UECA pole #270905 bears S 43°40' E, 5.65 feet.
- A 2" aluminum cap set on a 5/8" iron rod reference corner bears S 51°40'40" W, 93.82 feet.

MONUMENT MARKING DETAIL:

T5N R28E
 21 | 22
 28 | 27
 1995
 LS 951

MONUMENT SET:

New Accessories:

- The Northeast corner of the Northeast stand post of the Blue Mountain Asphalt tank bears N 62° W, 182.15 feet.
- All accessories have bearing object signs attached except stand post of Blue Mountain Asphalt tank.
- The witness corner has a steel fence post with witness post sign attached nearby.
- The corner has a steel fence post with witness post sign attached nearby.

LOCATION AND COMMENTS: Intersection of Bensel Road and Lind Road by Blue Mountain Asphalt. Note brass cap is marked 1995, not 1988. Find no record for the aluminum cap reference corner.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells
Benjamin Weinke

Oregon State Plane Coordinates, North Zone, NAD 83(91), Int. Feet:

North: 814175.73
East: 8505779.32

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

William R. Wells

OREGON
 JULY 22, 1977
 WILLIAM R. WELLS
 1106

Renews 6-30-98