

**OREGON CORNER RESTORATION FORM**

SECTION:31 TOWNSHIP: 5N

RANGE: 29E

V-1

COUNTY: UMATILLA

DATE: 12/05

**CORNER DESIGNATION**

NW Section 31

- CONDITION REPORT ONLY**
- NOT FOUND**
- RENEWED**
- UNRECORDED**
- SURVEYED IN**
- REFERENCED OUT**

**PREVIOUS RENEWALS/SURVEYS ETC.**

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound.

Kimbrell set 2" iron pipe in 1910

In 1974 Krumbain set brass cap 45' North

In 1984 Krumbain set 2 1/2" brass cap in place of Kimbrells 2" iron pipe.

**MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE**

Found 2 1/2" brass cap stamped as below.

W.C. found 2 1/2" brass cap (1974) it bears N 8° 05' 16" E 45.16'

**MONUMENT DETAIL**

T5N

S25 | S30

R28E S36 | S31 R29E

1984

P.L.S. 993

**OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:**

809006.30

8521773.95

**MONUMENT SET (PROCEDURES AND DESCRIPTION)**

**NEW ACCESSORIES FROM WHICH**

A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 78° 16' 16" E 36.53'

A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 21° 15' 34" W 68.23'

A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 36° 58' 06" E 56.93'

**LOCATION AND COMMENTS**

At the intersection of Ott road and Walls road.

FIRM: EDWARDS SURVEYING LLC  
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH  
WITNESS: J. JOSEPH

**SURVEYOR'S SEAL**

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
951

RENEWS 12/31/05