

OREGON CORNER RESTORATION FORM

Section: 1 – 2 – 35 – 36
Township: 5 North
Range: 28 East of the Willamette Meridian
County: Umatilla
Date: January 2024

Corner Indexing Information: Township 5N Range 28E Corner Code Z-21 (Willamette Meridian)
Additional Identifier: South standard section corner of Sections 35 & 36

Oregon Plane Coordinates: N: 803706.89 E: 8516555.16 **Zone:** North **Order:** second
Datum: NAD83-2011(epoch 2010) **Convergence:** N00°52'31"W **Scale Factor:** 1.000044268448

Previous Renewals/Surveys, etc.:

1861: Set post, mound, pits, & charred stake (Davenport, G.L.O. Contract #101)
1910: Corner found, not described (J. Kimbrell, C.S. 308)
1910: Corner found, not described (J. Kimbrell, C.S. 316)
1972: NF (Thompson, C.S. H-256)
1980: Found 1-1/2" pipe (inside dia.) with 1/2" I. pin inside. Records show pipe being used as late as 1910. Set brass cap in place of pipe for corner. (Krumbein, C.S. S-156-C)

Monument(s) & Accessories Found (Condition & Source):

2-1/2" brass cap per C.S. S-156-C, 0.3' deep, 1.5' north of the intersection of Glemm and Punkin center Rds.

Monument Set (Procedures & Description):

N/A

Monument Detail:

T5N R28E

S35 | S36
S1

T4N R28E

1980

LS 933

New Accessories: WE SET:

Set 5/8"x30" iron rebar with plastic cap marked "PBS WA-19619 OR-02820" at base of power pole, S83°20'28"W 312.92 feet from the corner; set bearing tag on adjacent power pole;
Set 5/8"x30" iron rebar with plastic cap marked "PBS WA-19619 OR-02820" at base of power pole, N50°50'06"W 52.17 feet from the corner; set bearing tag on adjacent power pole;
Set 5/8"x30" iron rebar with plastic cap stamped "PBS WA-19619 OR-02820" which bears S31°44'18"E 33.59 feet from the corner; attached bearing tag to the rebar;
Set 5/8"x30" iron rebar with plastic cap stamped "PBS WA-19619 OR-02820" which bears N55°56'44"E 58.91 feet from the corner; attached bearing tag to the rebar.

Location & Comments:

Corner lies at the intersection of E. Punkin Center Road and Glemm Road.


Compass Declination:

All accessories tied with State Plane grid bearings.

Firm/Agency: PBS Engineering & Environmental, Inc
5 N. Colville
Walla Walla WA 99362

Witness: Mark F. Wendover
Felipe Hernandez
Hayden Lomeli

Surveyor's Seal



OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/2025

2/14/2024