

OREGON CORNER RESTORATION FORM

SECTION 7, 18 TOWNSHIP 5 NORTH RANGE 29 EAST

J-3

COUNTY : UMATILLA DATE DEC/22

CORNER DESIGNATION

1/4 CORNER

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNCOVERED
- SURVEYED IN
- REFERENCED


PREVIOUS RENEWALS / SURVEYS, ETC.

SURVEYED IN 1861 BY DAVENPORT UNDER CONTRACT #101, HE SET POST AND MADE MOUND.
IN 1991 LS 951 SET A 2 3/8" BRASS CAP IN CONCRETE.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

FOUND 2 3/8" BRASS CAP STAMPED AS BELOW.
FOUND RAIL ROAD SPIKE STAMPED LS 951 BEARS N 00°06'17" E, 14.90'.
FOUND 5/8" IRON ROD WITH ALUMINUM TAG STAMPED LS 951 BEARS S 89°32'13" E, 63.81'.

MONUMENT DETAIL



NAD 83/91
OREGON STATE PLANE
INTERNATIONAL FEET

824918.98
8524204.83

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES FROM WHICH

SCRIBE IN NORTHEAST CORNER OF CONCRETE PAD BEARS S 85°28'24" W, 52.87'.
SCRIBE IN CONCRETE CURB BEARS S 00°02'29" W, 93.05'.

LOCATION AND COMMENTS

FROM NORTHWEST CORNER OF
WANAKET WILDLIFE AREA ON MCNARY
BEACH ROAD, GO EAST ALONG THE
NORTHERLY BOUNDARY +/- 1.5
MILES AND THEN GO NORTH +/-
0.25 MILE TO CORNER.

FIRM/AGENCY

PRIMM LAND SURVEYING, INC.
P.O. BOX 1322
HERMISTON, OREGON 97838

LAND SURVEYOR

BRIT L. PRIMM

WITNESS

KEITH P. PRIMM

SURVEYOR'S SEAL

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 13, 1999
BRIT L. PRIMM
48509

EXPIRATION DATE: 12/31/24