

OREGON CORNER RESTORATION FORM

SECTION: 18 TOWNSHIP: 5N RANGE: 29E J-5

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

NE 18

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract #101 in 1861. He set post and made mound. In 1951 Edwards found mound of stone set 2 1/2" B.C. in concrete.

MONUMENTS AND ACCESSORIES FOUND: CONDITON AND SOURCE

Found 2 1/2" BC in concrete. Stamped as detail. W.C. from which a 1" square iron tubing bears S 79° 36' 48" E 87.14' (87.18').

MONUMENT DETAIL

T5N R29E
 7|8
 18|17
 1991
 LS 951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

824942.72
8526851.36

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 1° 23' 05" W 54.67'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 82° 20' 40" W 24.72'
- A RR Spike stamped 951 bears N 2° 21' 48" E 40.75'

LOCATION AND COMMENTS

From NW corner of Wanaket Wildlife area on McNary Beach Road, go East 2 miles and North 0.25 miles to the corner. It lies 60' South of the edge of a bluff.

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/05