

**OREGON CORNER RESTORATION FORM**

SECTION: 15 TOWNSHIP: 5N RANGE: 29E N-17

COUNTY: UMATILLA DATE: 12/05

**CORNER DESIGNATION**

SE Section 15

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

**PREVIOUS RENEWALS/SURVEYS ETC.**

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound. In 1983 Edwards set a 1"x30" iron pipe with a 2 3/8 brass cap.

**MONUMENTS AND ACCESSORIES FOUND: CONDITON AND SOURCE**

Found 2 3/8" brass cap at the surface of the ground stamped as below.

**MONUMENT DETAIL**

T5NR29E  
15 | 14  
22 | 23  
1983  
L.S. 951

**OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:**

819878.48  
8542804.89

**MONUMENT SET (PROCEDURES AND DESCRIPTION)**

**NEW ACCESSORIES FROM WHICH**

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 78° 43' 06" E 24.49'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 66° 27' 55" W 26.08'
- A 5/8 x 30 Iron Rebar with plastic cap #951 bears S 44° 09' 20" W 83.09'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 10° 02' 51" E 83.51'

**LOCATION AND COMMENTS**

From intersection of hwy 730 with Hat Rock Road go Northwesterly on Hat Rock Road 0.25 miles. Corner lies just South of North R/W fence.

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC  
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH  
WITNESS: J. JOSEPH

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
951

RENEWS 12/31/05