

OREGON CORNER RESTORATION FORM

SECTION:28 TOWNSHIP: 5N RANGE: 29E R-11

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

N1/4 Section28

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound.
 Kimbrell set 2" iron pipe in 1910.
 In 1980 I drove 5/8" iron rebar into iron pipe.
 In 1991 I set 1"x3" iron pipe in concrete over 5/8" iron rebar.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

Found 2 3/8" brass cap stamped as below 8" below the surface of a graveled road.
 W.C. an aluminum tag 951 in a power pole bears N 34° 17' 14" W 32.75' (32.73').
 W.C. an aluminum tag 951 in a R/R tie fence post bears S 80° 01' 19" E 76.03' (76.00')

MONUMENT DETAIL

T5NR29E
 1/4 21
 28
 1991
 L.S. 951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

814459.12
 8534963.75

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES FROM WHICH

A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 64° 02' 06" E 64.84'
 A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 15° 13' 57" W 71.35'

LOCATION AND COMMENTS

At the intersection of Golda road and Progress road.

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
 PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
 WITNESS: J. JOSEPH

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

G. Dennis Edwards

OREGON
 JULY 16, 1971
 G. DENNIS EDWARDS
 951

RENEWS 12/31/05