

**OREGON CORNER RESTORATION FORM**

SECTION:27    TOWNSHIP: 5N    RANGE: 29E    R-17

COUNTY: UMATILLA    DATE: 12/05

**CORNER DESIGNATION**

NE Section 27

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

**PREVIOUS RENEWALS/SURVEYS ETC.**

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound. In 1981 survey for A.R.Z. Edwards computed the location of this corner from R/R ties.

**MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE**

Nothing found.

**MONUMENT DETAIL**

T5NR29E  
22 | 23  
27 | 26  
2005  
LS 951

**OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:**

814604.32  
8542895.43

**MONUMENT SET (PROCEDURES AND DESCRIPTION)**

By retracing Edwards 1981 survey for A.R.Z., I set a 1"x30" iron pipe in concrete with a 2 3/8" brass cap stamped as above flush with the ground.

**NEW ACCESSORIES FROM WHICH**

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 30° 48' 06" E 250.34'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 29° 25' 52" E 124.30'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 33° 49' 41" W 151.14'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 32° 34' 47" W 175.13'


**LOCATION AND COMMENTS**

From the intersection of Tabor road with Progress road, go East along Progress road and road projected East 1.00 mile. Corner lies just east of a fence that runs northwest.


SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC  
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH  
WITNESS: J. JOSEPH



*G. Dennis Edwards*



RENEWS 12/31/05