

# OREGON CORNER RESTORATION FORM

SECTION 19, 24, 25, 30 TOWNSHIP 5 NORTH RANGE 29 EAST, RANGE 30 EAST R-25  
COUNTY : UMATILLA DATE DEC/22

CORNER DESIGNATION  
SECTION CORNER

CONDITION REPORT ONLY  
 NOT FOUND  
 RENEWED  
 UNCOVERED  
 SURVEYED IN  
 REFERENCED


PREVIOUS RENEWALS / SURVEYS, ETC.

SURVEYED IN 1861 BY PAYNE UNDER CONTRACT #100, HE SET A POST AND MADE MOUND.  
IN 1970 HARRIS SET 1" X 36" IRON PIPE WITH BRASS CAP.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

FOUND 2 1/2" BRASS CAP STAMPED AS BELOW.  
FOUND 5/8" IRON ROD WITH YELLOW PLASTIC CAP STAMPED LS 951 BEARS N 79°20'15" E, 198.33'.  
FOUND 5/8" IRON ROD WITH YELLOW PLASTIC CAP STAMPED LS 951 BEARS S 68°41'31" W, 999.31'.  
FOUND 5/8" IRON ROD WITH YELLOW PLASTIC CAP STAMPED LS 951 BEARS S 12°04'52" W, 214.44'.  
FOUND 5/8" IRON ROD WITH YELLOW PLASTIC CAP STAMPED LS 951 BEARS S 88°38'55" E, 235.64'.

MONUMENT DETAIL



NAD 83/91  
OREGON STATE PLANE  
INTERNATIONAL FEET

814745.79  
8553439.29

MONUMENT SET ( PROCEDURES AND DESCRIPTION )

NEW ACCESSORIES FROM WHICH

LOCATION AND COMMENTS

FROM INTERSECTION OF COLD  
SPRINGS HIGHWAY AND WALLS ROAD  
GO SOUTHWEST ALONG WALLS ROAD  
+/- 1.35 MILES. CORNER FALLS  
+/- 150 FEET NORTHWEST OF  
ROAD.

FIRM/AGENCY

PRIMM LAND SURVEYING, INC.  
P.O. BOX 1322  
HERMISTON, OREGON 97838

LAND SURVEYOR

BRIT L. PRIMM

WITNESS

KEITH P. PRIMM

SURVEYOR'S SEAL

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 13, 1999  
BRIT L. PRIMM  
48509

EXPIRATION DATE: 12/31/24