

**OREGON CORNER RESTORATION FORM**

SECTION: 29 TOWNSHIP: 5N RANGE: 29E

R-7

COUNTY: UMATILLA

DATE: 12/05

**CORNER DESIGNATION**

N 1/4 Section 29

CONDITION REPORT ONLY  
 NOT FOUND  
 RENEWED  
 UNRECORDED  
 SURVEYED IN  
 REFERENCED OUT

**PREVIOUS RENEWALS/SURVEYS ETC.**

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound.  
In 1910 Kimbrell set iron pipe.  
In 1979 LaGier set a 5/8" iron rebar. It was 8' North & 26.6" West.  
In 2000 Roberts set a 5/8" iron rebar by single proportions.

**MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE**

Found 5/8" iron rebar with a 2" aluminum cap 4" below the surface stamped as below. See Monument Set.  
W.C. found 5/8" iron rebar with plastic cap 2627 bears N 13° 43' 46" E 85.17'(85.20')  
W.C. found 5/8" iron rebar with plastic cap 2627 bears N 35° 32' 16" W 111.86'(111.88')  
W.C. found 5/8" iron rebar with plastic cap 2627 bears N 74° 51' 13" W 28.22'  
W.C. found 5/8" iron rebar with plastic cap 2627 bears N 89° 14' 51" W 49.97'(50.00')  
W.C. found 5/8" iron rebar with plastic cap 2627 bears N 89° 14' 30" W 99.99'(100.00')

**MONUMENT DETAIL**

T5NR29E  
1/4 S20  
S29  
2000  
P.L.S. 2627

**OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:**

814382.98  
8529664.71

**MONUMENT SET (PROCEDURES AND DESCRIPTION)**

Monument has been disturbed .  
Moved it N 60° W 0.31 feet, drove to 6 " below surface and poured concrete around.

**NEW ACCESSORIES FROM WHICH**

**LOCATION AND COMMENTS**

From the intersection of Craig Rd. with Progress road. Go East 0.5 miles along a dirt road to corner.

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC  
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH  
WITNESS: J. JOSEPH

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
951

RENEWS 12/31/05