

OREGON CORNER RESTORATION FORM

SECTION: 28 TOWNSHIP: 5N

RANGE: 29E

T-13

COUNTY: UMATILLA

DATE: 12/05

CORNER DESIGNATION

E1/4 Section 28

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound. In 1979 LaGier set a 5/8" iron rebar in a survey for DeMoss.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

Found a 5/8" iron rebar 3" below the surface of a paved road.

MONUMENT DETAIL

T5NR29E
1/4
28 | 27

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

811881.99
8537657.39

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 46° 32' 05" E 30.90'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 52° 50' 11" W 46.53'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 41° 41' 09" W 35.48'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 41° 42' 02" E 19.02'

LOCATION AND COMMENTS

At the intersection of Spearman & Tabor roads.


SURVEYOR'S SEAL

**FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838**

**PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH**



G. Dennis Edwards



RENEWS 12/31/05