

# OREGON CORNER RESTORATION FORM

SECTION 25, 30 TOWNSHIP 5 NORTH RANGE 29 EAST, RANGE 30 EAST  
 COUNTY : UMATILLA DATE DEC/22

T-25

CORNER DESIGNATION

1/4 CORNER

CONDITION REPORT ONLY

NOT FOUND

RENEWED

UNCOVERED

SURVEYED IN

REFERENCED


PREVIOUS RENEWALS / SURVEYS, ETC.

SURVEYED IN 1861 BY PAYNE UNDER CONTRACT #100, HE SET A POST AND MADE MOUND.  
 IN 2005 LS 951 SET A 2 3/8" BRASS CAP 25" BELOW THE SURFACE OF A CULTIVATED CROP.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

FOUND 2 3/8" BRASS CAP STAMPED AS BELOW.  
 FOUND 5/8" IRON ROD WITH YELLOW PLASTIC CAP STAMPED LS 951 BEARS N 71°43'06" E, 499.52'.  
 FOUND 5/8" IRON ROD WITH YELLOW PLASTIC CAP STAMPED LS 951 BEARS N 15°29'32" W, 901.83'.  
 FOUND 5/8" IRON ROD WITH YELLOW PLASTIC CAP STAMPED LS 951 BEARS N 44°44'28" W, 1415.76'.  
 FOUND NORTHEAST BOLT OF PIVOT PAD BEARS S 66°35'59" W, 926.65'.

MONUMENT DETAIL



NAD 83/91  
 OREGON STATE PLANE  
 INTERNATIONAL FEET

N.T.S

812105.72  
 8553490.19

MONUMENT SET ( PROCEDURES AND DESCRIPTION )

NEW ACCESSORIES FROM WHICH

LOCATION AND COMMENTS

FROM INTERSECTION OF COLD SPRINGS HIGHWAY AND WALLS ROAD GO SOUTHWEST ALONG WALLS ROAD +/- 1.6 MILES, THEN GO SOUTHEAST BETWEEN 2 PIVOTS +/- 0.3 MILES. CORNER FALLS N 66° E, +/- 930 FEET FROM CENTER OF PIVOT.

FIRM/AGENCY

PRIMM LAND SURVEYING, INC.  
 P.O. BOX 1322  
 HERMISTON, OREGON 97838

LAND SURVEYOR

BRIT L. PRIMM

WITNESS

KEITH P. PRIMM

SURVEYOR'S SEAL

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Brit L. Primm*

OREGON  
 JULY 13, 1999  
 BRIT L. PRIMM  
 48509

EXPIRATION DATE: 12/31/24