

OREGON CORNER RESTORATION FORM

SECTION: 29 TOWNSHIP: 5N RANGE: 29E T-9

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

E1/4 Section 29

- CONDITION REPORT ONLY**
- NOT FOUND**
- RENEWED**
- UNRECORDED**
- SURVEYED IN**
- REFERENCED OUT**

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound.
In 1978 Krumbain set a 5/8" iron rebar.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

Found 1 1/2" aluminum cap 2" below the surface of a paved road. Illegible

MONUMENT DETAIL

T5NR29E
1/4
29 | 28

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

811765.24
8532368.26

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 19° 13' 42" E 13.69'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 36° 28' 42" W 27.18'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 73° 44' 52" W 63.86'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 43° 04' 11" E 28.46'

LOCATION AND COMMENTS

At the intersection of Spearman & Edwards roads.

SURVEYOR'S SEAL

**FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838**

**PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH**

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/05