

# OREGON CORNER RESTORATION FORM

SECTION 27, 28, 33, 34 TOWNSHIP 5 NORTH RANGE 29 EAST  
 COUNTY : UMATILLA DATE DEC/22

V-13

CORNER DESIGNATION  
 SECTION CORNER

CONDITION REPORT ONLY  
 NOT FOUND  
 RENEWED  
 UNCOVERED  
 SURVEYED IN  
 REFERENCED

PREVIOUS RENEWALS / SURVEYS, ETC.



SURVEYED IN 1861 BY DAVENPORT UNDER CONTRACT #101, HE SET POST AND MADE MOUND.  
 IN 1971 THOMPSON SET A 2 1/2" BRASS CAP.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

FOUND 5/8" IRON ROD.  
 FOUND 2 1/2" BRASS CAP W.C. STAMPED AS BELOW BEARS N 45°11'57" W, 46.58' (46.66').  
 FOUND 5/8" IRON ROD WITH PLASTIC CAP STAMPED LS 951 BEARS N 05°51'49" E, 183.91'.  
 FOUND 5/8" IRON ROD WITH PLASTIC CAP STAMPED LS 951 BEARS S 33°31'25" E, 31.20'.

MONUMENT DETAIL

2 1/2" BRASS CAP W.C.



NAD 83/91  
 OREGON STATE PLANE  
 INTERNATIONAL FEET

809243.62  
 8537704.42

MONUMENT SET ( PROCEDURES AND DESCRIPTION )

SET 2" ALUMINUM CAP STAMPED AS ABOVE OVER FOUND 5/8" IRON ROD.

NEW ACCESSORIES FROM WHICH

SET 5/8" X 30" IRON ROD WITH YELLOW PLASTIC CAP STAMPED PLS LS 48509 BEARS S 25°56'40" W, 40.67'.

LOCATION AND COMMENTS

CORNER FALLS AT INTERSECTION OF  
 WALLS ROAD AND TABOR ROAD.

FIRM/AGENCY

PRIMM LAND SURVEYING, INC.  
 P.O. BOX 1322  
 HERMISTON, OREGON 97838

LAND SURVEYOR

BRIT L. PRIMM

WITNESS

KEITH P. PRIMM

SURVEYOR'S SEAL

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Brit L. Primm*

OREGON  
 JULY 13, 1999  
 BRIT L. PRIMM  
 48509

EXPIRATION DATE: 12/31/24