

OREGON CORNER RESTORATION FORM

SECTION:26 TOWNSHIP: 5N RANGE: 29E V-19

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

S1/4 Section 26

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

Nothing found

MONUMENT DETAIL

T5NR29E
1/4 26
35
2005
L.S.951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

809367.32
8545622.11

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By single proportion I set a 1"x30" iron pipe in concrete with a 2 3/8" brass cap stamped as above 4" below the surface.

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 84° 37' 14" E 108.43'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 79° 53' 01" W 48.40'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 3° 16' 27" W 9.17'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 80° 48' 30" E 60.10'

LOCATION AND COMMENTS

From intersection of Marks road with Walls road go East on Walls road 0.5 miles to corner. Corner lies North of north R/W fence.

SURVEYOR'S SEAL

**FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838**

**PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH**

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/05